



NOTES:

1. EXISTING UTILITY INFORMATION SHOWN ON THESE PLANS IS FURNISHED BY THE UTILITY COMPANIES AND/OR THE SURVEYOR AND THE ACCURACY THEREOF IS NOT THE RESPONSIBILITY OF SCIULLO ENGINEERING SERVICES, LLC. IT IS THE RESPONSIBILITY OF THE OWNERS AND/OR CONTRACTOR TO CALL 1-800-272-1000 FOR FIELD LOCATION OF UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION.

- SEASONAL OR THEMED PLANTS SUCH AS HOLLY BUSHES, SMALL PALM TREES, OR OTHER EVERGREENS

PLANTER FILLED TO 6" BELOW RIM

— 28" PLASTIC PLANTER POT BY BLOEM

— FILTER FABRIC

PLANTER POT DETAIL

WIDTH VARIES — SEE PLAN

6" - 4,000 P.S.I. CONCRETE AT 28 DAYS

1. EXPANSION JOINTS SHALL BE 1/2" WIDE AND PROVIDED AT INTERVALS TO PREVENT

4. FINISH SHALL BE WOOD FLAT, FOLLOWED BY BROOMING TO A NEAT, WORKMANLIKE

CONCRETE DUMPSTER PAD DETAIL

3'-0" TYP.

4 4 4

2% SLOPE INDICATES FLOW AWAY FROM BUILDING TO ROADWAY OR PARKING AREA.

CONCRETE SIDEWALK DETAIL

N.T.S.

TO BE CORK OR MASTIC MATERIAL OR APPROVED EQUAL.

SIDEWALK SURFACE TO BE BROOM FINISH.

4. CONCRETE TO HAVE 8-10% AIR ENTRAINMENT.

CLASS "B" CONCRETE @ 4,500 PSI

1. EXPANSION JOINTS TO BE AT 20 FT C.C. CONTROL JOINTS TO BE AT 4 FT C.C. EXPANSION JOINT MATERIAL

CRACKING AND SHALL BE FILLED WITH 1/2" THICK CELLULAR COMPRESSION MATERIAL TO

2. SURFACE GROVES SHALL BE CUT AT LEAST 3/4" DEEP AT RIGHT ANGLES TO THE OUTSIDE

-COMPACTED SUBGRADE

REINFORCED WITH WIRE MESH

WITHIN 1/4" OF TOP OF PAD.

SURFACE EDGES SHALL BE ROUNDED TO 1/2" RADIUS.

— CLEAN, ROUND STONE

OR APPROVED EQUAL IN COLOR CHOSEN BY OWNER

- SEE FENCE DETAIL

AWAY FROM POLE

- 8'x11' INTERMODAL

±17'-0"

DUMPSTER PAD LAYOUT

N.T.S.

EXTEND DUMPSTER PAD

FLUSH TO EXISTING SIDEWALK

STORAGE CONTAINER

4' HIGH

WOOD FENCE

(SEE DETAIL)

▶ 6" CONCRETE

DUMPSTER PAD

(SEE DETAIL)

(SEE DETAIL)

2. THESE PLANS ARE NOT FOR CONSTRUCTION UNTIL "ISSUED FOR CONSTRUCTION" APPEARS IN THE TITLEBLOCK.